LEVEL II ENVIRONMENTAL SITE ASSESSMENT LOT 1, BLOCK 4, CHEYENNE AIRPORT ADDITION CHEYENNE, WYOMING

PROJECT NO. 24947002



A Division of The Terracon Companies, Inc.

DEVEL HE NY ROYMENT LESSENSENS SELECTED ASSESSENSENS OUR PENNE ATTRONG ADDA SON CESTE ENGL, WYOMENG

THE STATE OF THE PARTY OF THE P



to palauta A Lind Far audit Companies (alf Gill F

LEVEL II ENVIRONMENTAL SITE ASSESSMENT LOT 1, BLOCK 4, CHEYENNE AIRPORT ADDITION CHEYENNE, WYOMING

PROJECT NO. 24947002

PREPARED BY

EMPIRE LABORATORIES, INC.
A DIVISION OF THE TERRACON COMPANIES, INC.

November 8, 1994

Empire Laboratories, Inc.

A Division of The Terracon Companies, Inc.



Empire Laboratories, Inc.

A Division of The Terracon Companies, Inc.

P.O. Box 503 • 301 No. Howes Fort Collins, Colorado 80522 (303) 484-0359 Fax (303) 484-0454

Chester C. Smith, P.E. Larry G. O'Dell, P.E. Neil R. Sherrod, C.P.G.

November 8, 1994

Southwest Partners, Ltd. Corporate Real Estate Services 2801 East Camelback Road, Suite 105 Phoenix, Arizona 85016

Attn: Mr. Larry LaPrade

RE: Limited Level II Environmental Site Assessment Lot 1, Block 4, Cheyenne Airport Addition

> Cheyenne, Wyoming Project No. 24947002

Dear Mr. LaPrade:

Empire Laboratories, Inc. (Empire) has been completed a Limited Level II Environmental Site Assessment for the above-referenced property in general accordance with our proposal No. 2094376 dated October 14, 1994. A Phase I Environmental Site Assessment (Phase I ESA) was performed at the subject site by Inberg-Miller Engineers (IME) of Cheyenne, Wyoming. Based upon information obtained by IME and the known historical usage of the site, IME recommended that a Level II Site Assessment be performed. The purpose of the Level II Site Assessment was to 1) monitor for the presence of possible petroleum hydrocarbon contamination along with 8-RCRA dissolved metals, polychlorinated biphenyls (PCBs) and volatile organic compounds (VOCs) and 2) if observed, to assess the significance of such contamination.

Our field services included the completion of three (3) soil borings and installation of three (3) groundwater monitoring wells (GMW) to depths of approximately twenty (20) to twenty-two (22) feet below the surface, collection of water samples, and chemical analyses of water samples obtained from each GMW. Groundwater was observed in the soil borings completed at the site at depths ranging approximately from thirteen (13) to fifteen (15) feet below the surface. Obvious signs of significant petroleum hydrocarbons, 8-RCRA metals, PCBs and/or VOCs were not observed in water samples collected from the site with the exception of 1,1-dichloroethene, 1,2-dichloroethane and trichloroethene observed in GMW No. 1 as well as relatively high levels of tetrachloroethene (TCE) observed in the water sample collected from GMW No. 2. Please refer to the attached engineering analyses report for further details.

We appreciate the opportunity to be of service to Southwest Partners on this project and are prepared to assist you with any future environmental engineering concerns at the site. If there are any questions concerning this Limited Level II Environmental Site Assessment report, please feel free to contact us at (303) 484-0359.

Very truly yours,

EMPIRE LABORATORIES, INC.

A DIVISION OF THE TERRACON COMPANIES, INC.

David A. Richer, P.E.

Project Engineer

Scott A. Rutherford, P.E.

Wyoming No. 6435

DAR/SAR:dmf3

500

11/8/94

TABLE OF CONTENTS

	Page
1.	INTRODUCTION
2.	PROJECT SCOPE
3.	SUBSURFACE EXPLORATION
4.	SUBSURFACE SOILS
5.	GROUNDWATER OBSERVATIONS 6
6.	CONTAMINANT CHARACTERISTICS
7.	CONCLUSIONS AND RECOMMENDATIONS
8.	GENERAL COMMENTS
APPI	ENDICES
APPI APPI APPI	ENDIX A - FIGURES ENDIX B - BORING LOGS ENDIX C - FIELD METHODS ENDIX D - TABLES ENDIX E - LABORATORY TEST RESULTS

LIMITED LEVEL II ENVIRONMENTAL SITE ASSESSMENT LOT 1, BLOCK 4, CHEYENNE AIRPORT ADDITION CHEYENNE, WYOMING

Terracon

Project No: 20947002 Date: November 8, 1994

1. INTRODUCTION

The purpose of this limited Level II Environmental Site Assessment was to provide information regarding possible environmental risks associated with the subject property based upon known historical usage of the property as well as information contained in a Phase I Environmental Site Assessment (Phase I ESA) report prepared by Inberg-Miller Engineers (IME) of Cheyenne, Wyoming. IME's report, "there is a moderate to high risk that the site has been adversely impacted by on-site and/or off-site activities." This was based on the fact that the subject site at one time was utilized as the original Cheyenne airport hangars site as well as the United Airlines maintenance/overhaul facility until 1947. site presently is a vacant tract of land. It is also our understanding that the Wyoming Department of Environmental Quality/Water Quality Division (WDEO/WOD) had encountered chlorinated solvent contamination in a private irrigation well located approximately two blocks downgradient relative to the subject property. IME recommended that a subsurface contamination evaluation (Level II Environmental Site Assessment) be performed at the subject site. Southwest Partners (SWP) retained Empire Laboratories, (Empire) to conduct a limited Level Inc. Environmental Site Assessment at the site located at the northeast corner of Central Avenue and 8th Avenue in Cheyenne, Wyoming. general location of the subject property is shown as Figures 1 and 2 of Appendix A.

The subject property is described as a tract of land situate in the southeast quarter of the northwest quarter of Section 30, Township 14 North, Range 66 West of the 6th P.M., Laramie County, Wyoming. The subject site consists of the triangular shape property located

north of 8th Avenue, west of Warren Avenue and east of Central Avenue. A site location diagram is included as Figure 3 in Appendix A of this report.

2. PROJECT SCOPE

Empire conducted a limited Level II Environmental Site Assessment at the subject property on October 25, 1994. The purpose of the site assessment was to provide SWP with information regarding possible petroleum hydrocarbon, 8-RCRA dissolved metals, PCBs and volatile organic compound (VOC) contamination of groundwater beneath the subject site. The following tasks were performed in general accordance with Empire's proposal No. 2094376 dated October 14, 1994.

- Completed three (3) soil borings and installed three (3) groundwater monitoring wells (GMW) at the site to obtain information regarding possible subsurface soil and groundwater contamination. The soil borings were completed to depths of approximately twenty (20) to twenty-two (22) feet below existing site grades. The soil borings were drilled as shown on Figure 3 at the southeast and southwest corners of the site as well as along the northeast property line. Soil samples were collected from the soil borings and screened on site with a photoionization detector (PID) using ambient temperature headspace analysis (ATHA).
- The groundwater samples collected from the three (3) GMWs were transported under standard Empire chain-of-custody procedures to Technology Laboratories, Inc. (TLI) in Fort Collins, Colorado for analyses of VOCs, total volatile petroleum hydrocarbons (TVPH), total extractable petroleum hydrocarbons (TEPH), oil and grease, 8-RCRA dissolved metals and PCBs.
- Prepared an engineering report which contains a summary and evaluation of the collected data, conclusions and recommendations.

These tasks were performed in an effort to obtain information regarding the presence of significant petroleum hydrocarbon

D

Project No. 24947002 November 8, 1994 Page 3

contamination, metals, PCB and/or VOC contamination beneath the subject site.

3. SUBSURFACE EXPLORATION

The locations of the GMWs completed at the site are shown on Figure 3 in Appendix A. The GMWs completed as part of this limited Level II Environmental Site Assessment are referred to as GMW Nos. 1 through 3. As seen from Figure 3, the GMWs were placed in a triangle configuration at the site in an effort to obtain a representation of the soil and groundwater profile at the subject site. Soil samples were collected during the subsurface exploration operations using hollow-stem auguring and split-spoon sampling techniques. The methods used to perform the field sampling and soil boring operations are presented in Appendix C of this report.

The borings were advanced with a truck-mounted drilling rig utilizing 3½ inch inside diameter hollow stem augers. The GMWs were located by Empire from existing property lines using conventional chaining methods. Elevations were taken of the ground surface of each GMW as well as the top of casing (TOC) of each GMW by measurements with an engineer's level and referenced to a temporary bench mark (TBM) as shown on the Site Plan, Figure 3. The accuracy of boring locations and elevations should only be assumed to the level implied by the methods used.

Details of the GMWs are provided on the boring logs included in Appendix B. The GMWs were cased with 2-inch diameter Schedule 40 flush-jointed threaded PVC pipe. The lower 10 feet of the PVC pipe consisted of 0.02-inch slotted screen. The wells were backfilled with No. 10-20 silica sand to approximately 2 feet above the top of the well screen pipe and approximately 2 feet of bentonite clay

pellets were placed above the silica sand. The remainder of the GMWs were backfilled with a non-shrink cement grout material. An 8-inch diameter flush grade locking well cover was placed at the surface of each GMW for protection.

Initial and 24-hour water table levels were measured to obtain information regarding groundwater conditions at the site. Groundwater was observed during the drilling operations and 24 hours after drilling at depths of approximately 13% to 15 feet below the surface. Development of the GMWs was performed to obtain stabilized groundwater elevations and to estimate the piezometric surface for the site. A groundwater contour map was developed from groundwater elevations observed on October 26, 1994 and is included as Figure 4 in Appendix A of this report. The piezometric surface was estimated using linear interpolations between monitor wells and was based upon groundwater table elevation measurements from GMW Nos. 1, 2 and 3. As illustrated on Figure 4, the groundwater flow was estimated to be in the southeasterly direction. It should be noted local hydrogeologic characteristics such as flow direction and gradient may change due to variations in precipitation, recharge and other conditions not evident at the time of the field exploration.

Boring logs prepared from the field logs are also included in Appendix B. Final boring logs included in this report represent our interpretation of the field logs. These logs show soils encountered, location of sampling and groundwater at the time of the field exploration as well as the cross-section of each GMW. The stratification boundaries shown on the attached boring logs represent the approximate locations of changes in soil types; insitu the transition of materials may be gradual. During the drilling operations, a geo-environmental engineer from Empire was present and made observations of the soils encountered.

C

Project No. 24947002 November 8, 1994 Page 5

Lithologic logs of each GMW were recorded by the geo-environmental engineer during the drilling operations. At selected intervals, samples of the subsurface materials were taken by means of driving a split-spoon sampler. The split-spoon sampler was cleaned between each use. The hollow stem augers and the split-spoon sampling device were cleaned prior to or between each test boring to reduce the possibility of cross contamination between test borings. Soil samples during the drilling operations were screened on site using a photoionization detector (PID).

Soil samples were collected for ATHA at varying intervals from each soil boring using split-spoon sampling techniques. procedure is described in Appendix C. ATHA is a qualitative indicator of volatile organic contamination and should not be quantitative of volatile measure organic construed as a contamination. Boring logs prepared from the field logs along with the PID readings observed during ATHA are summarized in the Log of Borings in Appendix B. As illustrated from the boring logs, organic vapors were observed at one (1) part per million (ppm) in the soil samples collected from GMW Nos. 1 through 3.

4. SUBSURFACE SOILS

Descriptions of the soils encountered in the GMWs are provided on the boring logs which are included in Appendix B. Those descriptions are in general accordance with the General Notes also included in Appendix B. The stratification boundaries shown on the attached boring logs represent the approximate locations of changes in soil types; in-situ, the transition of materials may be gradual. Final boring logs included in this report represent an interpretation of the field logs as well as the cross-sectional construction of the monitoring wells.

Based on the results of the field logs, the subsurface conditions can be generalized as follows.

- 1. Fill Material. A 3½ to 4 foot layer of fill was encountered at the site. The fill consists of a mixture of gravel, silt and sand with pieces of concrete, brick and clay tile.
- 2. Sand with Gravel. This granular stratum was encountered below the fill at depths of approximately 3% to 4 feet below the surface and extends to the bedrock below. The sand and gravel is poorly graded, dense to very dense, and non-plastic in its dry to saturated in-situ condition.
- 3. <u>Sandstone-Siltstone-Claystone Bedrock.</u> The bedrock was encountered below the sand with gravel stratum and extends beyond the depths explored. The bedrock is part of the poorly consolidated sediments of the Ogallala Formation. In general, the bedrock is highly weathered.
- 4. Groundwater. At the time of the exploration, free groundwater was encountered at depths of approximately 13% to 15 feet below the surface. Water levels in this area are subject to change due to seasonal variations and/or irrigation demands on and/or adjacent to the property.

Please refer to the boring logs in Appendix B for a graphical representation of the materials encountered in GMW Nos. 1 through 3.

5. GROUNDWATER OBSERVATIONS

Groundwater was observed during drilling operations at depths ranging from approximately thirteen and one-half (3½) to fifteen (15) feet below the ground surface in GMW Nos. 1 through 3. Installation and development of groundwater monitoring wells was required to obtain stabilized groundwater elevations and to estimate a piezometric groundwater surface for the site. Based on initial and 24-hour groundwater elevation levels encountered at the site, the groundwater directional flow was estimated to be in a southeasterly direction. It should be noted that local

geohydrologic conditions may change due to variations in stratigraphy, precipitation and recharge or other conditions not evident at the time of the field exploration.

6. CONTAMINANT CHARACTERISTICS

A groundwater water sample was collected from each GMW for TVPH, TEPH, oil and grease, 8-RCRA dissolved metals, PCBs and VOC analyses. The groundwater samples were collected from cased and developed groundwater monitoring wells which were installed at the site on October 25, 1994. Copies of TLI laboratory reports for the groundwater samples collected at the subject site are included in Appendix E of this report. The groundwater sample results are summarized in Sections 6.1.

6.1 Groundwater Sample Results

Groundwater samples were collected from the three (3) GMWs on October 26, 1994. The laboratory test results are included in Appendix E of this report. The location of the GMWs are shown on Figure 3 in Appendix A. The groundwater samples were analyzed for TVPH, TEPH, oil and grease, 8-RCRA dissolved metals, PCBs and VOCs.

As shown on the laboratory test results, TVPH, TEPH, oil and grease, 8-RCRA metals, PCBs and VOCs were not observed above the laboratory detection limits in the groundwater samples collected from MW Nos. 1 through 3 with the exception of 15 different VOCs analyzed from a total of 54 VOCs tested. The results of observed VOC concentrations encountered in GMW Nos. 1 through 3 are summarized on Table 1 included in Appendix D. The remaining VOC laboratory test results for GMW Nos. 1 through 3 indicate that the analytes were not observed above the laboratory detection limits.

As seen from Table 1, VOC contaminant concentrations observed in groundwater samples analyzed from GMW Nos. 1, 2 and/or 3 consisted of 1,1-dichlorethyene, 1,1-dichloroethane, 1,1,1,-trichloroethane, 1,2-dichoreothane, trichloroethene, 1,2-dibromoethane, naphthalene, ethylbenzene, xylenes, total tetrachloreothene, trimethylbenzene, 1,2,4-trimethobenzene, tert-butylbenzene, benzene and toluene. The 15 compounds observed in the VOC, EPA Test Method 8260, in the GMW Nos. 1 through 3 were compared to the Wyoming Department of Environmental Quality/Water Quality Division (WDEO/WQD) maximum contaminant levels (MCLs). The MCLs were derived from the Federal EPA Groundwater Standards. As seen from Table 1, the drinking water equivalent levels (DWEL) were also used to analyze and compare the concentrations observed from groundwater samples collected from GMW Nos. 1 through 3. As seen from Table 1, four (4) of the fifteen (15) VOC compounds encountered in the groundwater samples collected from GMW Nos. 1 through 3 exceeded the WDEQ MCLs. The compounds which exceeded the WDEQ MCLs were 1,1-dichloroethene, 1,2-dichloroethane, trichloroethene encountered in GMW No. 1 and tetrachloroethene encountered in GMW No. 2. The remaining VOC concentration levels encountered in GMW Nos. 1, 2 and 3 did not exceed the WDEQ MCL or DWEL limits.

Tetrachloroethene, also known as perchloroethylene (PCE) encountered in MW No. 2, is a common industrial solvent used for dry cleaning and/or degreasing. The groundwater standard for PCE is 5 ug/L. That standard is the WDEQ/WDQ MCL limit. The concentration of PCE at 108 ug/L observed in MW No. 2 water sample exceeded the PCE groundwater standard. Based on the groundwater flow direction, it appears that the PCE contamination possibly is migrating onto the subject site from an upgradient source.

Empire contacted personnel with the WDEQ/WQD to ascertain the significance of the level of PCE contamination encountered at the

Information pertaining to preliminary groundwater directional flow, levels and locations of PCE contamination site, characteristics of PCE, encountered at the possibility of off-site sources impacting the subject property were discussed. A representative with the WDEQ/WQD indicated that the PCE levels were significant, yet the WDEQ has no plans to take action to remediate the contamination. The WDEQ/WQD representative also mentioned that SWP would not be responsible for future site remediation. It is Empire's opinion that the PCE contamination impacting the subject site is caused by an upgradient off-site source, i.e. northwest of the site. It is also Empire's opinion that SWP should not be responsible for groundwater remedial activities if in fact the source of the PCE contamination is from an off-site upgradient facility.

7. CONCLUSIONS AND RECOMMENDATIONS

The following conclusions were drawn from the information obtained during the Level II Site Assessment conducted at the subject site:

- 1. Organic vapors were observed at one (1) ppm range in the soil samples collected from MW Nos. 1 through 3.
- 2. Surficial deposits encountered at the site consisted of a silty sand with varying amounts of sand and gravel. These materials are relatively permeable and would allow for relatively rapid migration of groundwater contamination.
- 3. Groundwater was observed during drilling operations at depths ranging from approximately 13½ to 15 feet below the surface in MW Nos. 1 through 3. The groundwater flow direction for the subject site was estimated to be in a southeasterly direction.
- 4. TVPH, TEPH, oil and grease, 8-RCRA dissolved metals, PCB and VOCs were not observed above the laboratory detection limits for the water samples collected from MW Nos. 1 through 3 with the exception of 15 of 54 compounds analyzed in the VOC, EPA Test Method 8260.

- 5. Concentrations of 1,1-dichoroethene, 1,2-dichloroethane and trichloroethene observed in the groundwater sample collected from GMW No. 1 slightly exceeded the Wyoming Groundwater Standards. The source of that contamination may or may not be the subject site. Additional exploration would be required to obtain information regarding the source of the contamination.
- 6. The concentration of PCE observed in the groundwater sample collected from GMW No. 2 exceeded the Wyoming Groundwater Standard.
- 7. It appears that the PCE contamination is migrating onto the subject site from an upgradient direction, i.e. the northwest. Additional exploration would be required to confirm this preliminary conclusion.

The following recommendations are made based on information obtained during the Level II Site Assessment conducted at the subject site.

- Groundwater contained in the uppermost, alluvial aquifer beneath the site should not be used for drinking water or other purposes without treatment.
- 2. It is suggested that SWP and/or the present owners notify the WDEQ/WQD of the results of this assessment and that PCE appears to be migrating onto the site from an off-site source. Written confirmation should be obtained from the WDEQ/WQD regarding their evaluation of the site.

8. GENERAL COMMENTS

The analyses and opinions expressed in this report are based upon data obtained from water samples collected at the indicated locations. This report does not reflect any variations in subsurface topography, geohydrology or contaminant distribution which may occur between borings and/or across the site.

This report was prepared for the exclusive use of SWP for specific application to the subject project and has been prepared in accordance with generally accepted geo-environmental engineering


C

Project No. 24947002 November 8, 1994 Page 11

practices. No warranties, either express or implied, are intended or made. In the event that any changes in the nature or location of suspected sources of contamination as outlined in this report are observed, the conclusions and recommendations contained in this report shall not be valid unless these changes are reviewed and the opinions of this report are modified in writing by Empire.

APPENDIX A

FIGURES




П

-

w


0

D



SOUTHBOUND DENTRAL MW.2 STE AVENUE SCALE 60 120 1=601 GROUNDWATER AIRPORT ADDITION B-00-4, Empire Laboratories, Inc.
A Division of the
Terracon Companies Job : 24947002 Date Nov. 1994 Drawn 1/2

U




APPENDIX B
BORING LOGS

HARRIOTE LANGE

Vestigation and the first state of B.

	MONITORING WELL # 1 Page 1 of 1												
CLI	CLIENT Southwest Partners					ARCHITECT/ENGINEER							
				PROJECT Limited Level II E.S.A.									
			WELL SAMPLES				-	ESTS					
HIC LOG	DESCRIPTION		DET	AIL	H (FT.)	SYMBOL	ER .		JERY	N S / FT.	MOISTURE, %	UNCONFINED	ENGS
GRAPHIC	TOP OF CASING ELEV.: APPROX. SURFACE ELEV.:	98.9 ft. 99.0 ft.			DEPTH	SOSA	NUMBER	TYPE	RECOVERY	SPT - BLOWS	MOIS	UNCOL	PID READINGS PPM
	FILL-Silty clayey sand with gravel Brown, moist Non-shrink Grout		() ()	7777									
\bowtie	5.0	94.0			_		1	SS	12"	19			1
				1	5 —		2	SS	12"	14			
	SILTY SAND WITH GRAVEL Tan/gray, dry to moist Medium dense to dense		1 1 1	1111									
	Bentonite clay				=			za i					
- 1					10		3	SS	12"	50			1
-					=		4	SS	12"	50			
	13.5	₹ 85.5											
	Silica sand				15		5	SS	12"	9			1
		1				\dashv			12"	15			
	WEATHERED CANDSTONE				-	+		\dashv					
	WEATHERED SANDSTONE/ CLAYSTONE/SILTSTONE OGALLALA FORMATION Tan/gray, moist												
	Moderately hard to hard				20 +	\dashv	7	SS	12"	18			1
	21.5	77.5			+		8	SS	12"	36	4.4		
V///	BOTTOM OF BORING	11.5											
THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY LINES BETWEEN SOIL AND ROCK TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL. BETWEEN SOIL AND ROCK TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL. BETWEEN SOIL AND ROCK TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL. BETWEEN SOIL AND ROCK TYPES: IN-SITU, THE TRANSITION MAY BE GRADUAL.													
	WATER LEVEL OBSERVATIONS					BORING STARTED 10-25-9			SCORES CONTRACTOR DE CONTRACTO				
		Empire Laboratories Incorporated				-	BORING COMPLETED					10-25-	
WL WL	TOP OF	Division of Terracon				-	RIG CME-55 FOREM APPROVED SAR JOB #				DAR		
1177	Water checked 1 day A.B.		MAN STREET	MACO MICH	Consequence	P	APPK(JAED	5	SAR	JOB #	24	947002

CLI	ENT	MONITORI									De	no 1 - 0	
	Southwest Partners	80320000000000	ARCHIT	ECT/E	ENGIN	EER					Pa	ge 1 of	
SITE	E Lot 1, Block 4, Cheyenne Airport	Addition	PROJEC'	Г				77197	You'll t	-wat	eci?		
	Cheyenne, Wyoming	- Addition	INOJEC	ı		Limi	tod 1		II r	no gadi	146	off .	
CD	8.6.6.0.0	Manager 1	WELL		T	Limited Level II				TESTS			
700	DESCRIPTION		DETAIL	^	٦					1 %	12513	7	
			70,20	(FT.)	SYMBOL				F	60			
GRAPHIC	TOD OF CLOSE SECTION				Sγ	2		RECOVERY	Z	MOISTURE,	STH	SON	
GRA	TOP OF CASING ELEV.: APPROX. SURFACE ELEV.:	97.3 ft.		DEPTH	nscs	NUMBER	TYPE	50	- Z	ST	NON NO	DIO	
- XX	TOTAL MENT OF THE PROPERTY OF	97.5 ft.		日	Sn	N	Y	RE	SPT - BLOWS	M E	UNCONFINED	PID READINGS	
\bowtie	FILL-Silty clayey			_				-		-			
\bowtie	sand with gravel Brown, moist			-			-			ieuro:		Andrew S	
\bowtie	= 10 WH, MOISt						4			12	CER S	FORK.	
\bowtie	3.5 Non-shrink	Grout	7 7										
	ELVA OIT III	94.0	111	_		190	الما	dile.					
+			111	· -									
+			1 1	5		1	SS	12"	8			1	
1					+	2	SS	12"	23			1	
-						-	55	12	23				
	Benton	ite clay		-									
1	CIV TIVE CARE		4 4				2836						
1	SILTY SAND WITH GRAVEL Tan/gray, dry to moist			+				77			240		
+	Medium dense to dense			7	_	_				77.4	LEGAL .		
1	asino to dollac		1	0 —		3	SS	12"	37	176 9	ish in	1	
I	<u>Sil</u>	ica sand	目	7		4	SS	2"	44				
+	12.0		:目:十	+				+		-			
*	13.0	84.5	目丨	-									
		₹		1					-				
			目	+									
			1:	5		5 S	S 1	2"	16	-	1		
				士		6 S	S 1	2"	41	-	^		
	WEATHERED SANDSTONE/			7	-	-	- 1	_	71				
	CLAYSTONE/SILTSTONE		目:	1			_ 8	MI		£ 0 £			
	OGALLALA FORMATION Tan/gray, moist		目:	4.					31/4				
	Moderately hard to hard			1			100	y an	ishorn	12 7			
1				+		7 S	S 12	2"	10	7 7	1		
2	1.0	76.5	20	1		8 S	S 12	2" 2	40	\dashv			
1	BOTTOM OF BORING	70.5		+		+	+	-					
1						1					1 CP		
STRA	TIFICATION LINES REPRESENT THE APPROX	TMATE BOUNDARY 1711			Den			THE SECOND					
DESCRIPTION OF THE PARTY OF THE	THE TRUE THE TRUE THE TR	ANSITION MAY BE GRAD	UAL.		BORE WELI	HOL	E DIA	\.: (6.0 in	MASK A	alesa (a	DIT LA	
WA	TER LEVEL OBSERVATIONS				BOI	RING	STAF	TED			k Prov	THE RESERVE AND ADDRESS OF THE PARTY OF THE	
<u></u>	13.7' W.D. ₹ 13.4' T.O.C.	Empire Labo	ratori	es	-		7.0	PLET	FD)-25-9		
	top of casing	Incorpor	ated		RIG)-25-94		
		day A.B. Division of Terrac				RIG CME-55 APPROVED SAR				FOREMAN DAR			



U

APPENDIX C

FIELD METHODS

porings are shown on Figure 3 in Appeadix A. The drilling services or partings are prelighed by a three-man draw consisting of a drillier, a driller's helper and a geotechnical engineer. The Empire engineer nicerpreted substitutes conditions and collected soil samples dozing infilling services. The GMW were completed with a bruck-mounted. Infilling equipped with a hydraulic head employed in drilling no sampling operations. The GMW were advanced daing 3.25-inch noide diameter (1.5) hollow shes advanced daing 3.25-inch dyenced to depths of between approximately 30 and 22 feet balow.

П

D

Field logs of each boring were prepared by the impine engineer.

These logs contain visual tactual classifications of the marerials encountered during dralling, as well as the artificity of subscriber conditions has don't interpretation of subscriber conditions.

Soil damping ware obtained from the Mos. I through 3 using spillspoon sampling techniques. Suils encountered while drilling ware
screened on site for erganic vapors with a procountsation detector
(PID) to aid in determining potential gones of oreside vapor
contamination. Soil samples were soiledted at verious intervals
for ambient temperatura handspace thatysis (ATEA). The AVEA
procedure consists of transferring the soil samples from the
spitt coors insigned and fill of the contamination was allowed to

FIELD METHODS

Groundwater Monitoring Wells

The groundwater monitoring wells (GMW) were completed at the subject property on October 25, 1994. The locations of the GMW borings are shown on Figure 3 in Appendix A. The drilling services were performed by a three-man crew consisting of a driller, a driller's helper and a geotechnical engineer. The Empire engineer interpreted subsurface conditions and collected soil samples during drilling services. The GMW were completed with a truck-mounted, drilling rig equipped with a hydraulic head employed in drilling and sampling operations. The GMW were advanced using 3.25-inch inside diameter (I.D.) hollow-stem augers. The augers were advanced to depths of between approximately 20 and 22 feet below the ground surface. Excess auger cuttings were left on site.

Field logs of each boring were prepared by the Empire engineer. These logs contain visual-tactual classifications of the materials encountered during drilling, as well as the driller's interpretation of subsurface conditions based on drilling resistance and difficulty.

Soil Sampling

Soil samples were obtained from GMW Nos. 1 through 3 using splitspoon sampling techniques. Soils encountered while drilling were screened on site for organic vapors with a photoionization detector (PID) to aid in determining potential zones of organic vapor contamination. Soil samples were collected at various intervals for ambient temperature headspace analysis (ATHA). The ATHA procedure consisted of transferring the soil samples from the split-spoon samplers into Ziplock bags such that the bags were approximately one-third full. allowed The sample was equilibrate with the container headspace for approximately 15 minutes. The probe of the PID was then used to pierce the bag and the maximum observed reading was recorded. ATHA results are

Field Methods Project No. 24947002 November 8, 1994 Page C2

summarized on the boring logs in Appendix B. ATHA results are considered only a qualitative field measurement of contamination and should not be interpreted as quantitative analyses.

Groundwater Sampling

Groundwater samples were collected from GMW Nos. 1 through 3 on October 26, 1994 with disposable bailers and placed in sample containers. The sample containers consisted of 40-ml vials with Teflon septa as well as 1-L amber glass bottles. The groundwater samples were placed in a cooler with ice and transported to Technology Laboratory, Inc. in Fort Collins, Colorado for chemical analyses.

Cleaning Operations

Sampling equipment, drilling equipment and the drill rig were cleaned with a high-pressure, hot-water washer prior to entering the site and prior to leaving the site. The sampling equipment were also cleaned between borings using a high-pressure, hot-water washer. Wash water from cleaning of the drilling equipment was discharged on site.

Surveying

The GMWs were surveyed after completing the subsurface exploration. The GMW locations and elevations were surveyed by Empire. The elevations of the GMWs are relative to the temporary benchmark consisting of the north bonnet bolt of the fire hydrant located along the south portion of the site (Site Plan Figure 3 in Appendix A).

Field Methods Project No. 24947002 November 8, 1994 Page C3

Safety Protocol

Field services were performed by Empire personnel using level D personal protective procedures. These procedures included the use of hard hats, rubber gloves, and steel toed boots by drilling personnel.

APPENDIX D TABLES

SUMMARY OF GROUNDWATER LABORATORY TESTS RESULTS **EPA TEST METHOD 8260** TABLE 1

PROJECT: Lot 1, Block 4, Cheyenne Airport Addition CLIENT: Southwest Partners PROJECT NO: 24947002

									-						
Wyoming Groundwater Standards (ug/L)	7.0	3,000	200	5.0	5.0	NR	1,300+	2	700	10,000	10+	16+	NR	5	1,000
MW-3 (ug/L)	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	2.6	<0.5	1.2	6.9	0.8	3.0	9.0	2.2	5.5
MW-2 (ug/L)	<0.5	<0.5	<0.5	5.8*	5.3*	1.1	5.6	108*	6.0	1.6	2.8	9.6	1.3	<0.5	<0.5
MW-1 (ug/L)	16.6*	20.7	39.3	5.8*	5,3*	1.1	1.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5	<0.5
Compound Analyzed	1,1-Dichloroethene	1,1-Dichloroethane	1,1,1-Trichloroethane	1,2-Dichloroethane	Trichloroethene	1,2 Dibromoethane	Naphthalene	Tetrachloroethene	Ethylbenzene	Total Xylenes	1,3,5-Trimethylbenzene	1,2,4-Trimethylbenzene	Tert-butylbenzene	Benzene	Toluene
CAS	75-35-4	75-34-3	71-55-6	107-06-2	79-01-6	106-93-4	91-20-3	127-18-4	100-41-4	-	108-67-8	95-63-6	9-90-86	71-43-2	108-88-3

The sample locations are shown on the Site Plan, Figure 3 in Appendix A. NOTES:

+ Denotes DWEL = Wyoming Drinking Water Equivalent Levels, Groundwater Standards.

Wyoming Groundwater Standards, MCL = Maximum contaminant levels unless otherwise indicated with an (+) for DWEL. - 36.46

NR = Not regulated.

*Denotes exceeds Wyoming Groundwater Standard

APPENDIX E LABORATORY REPORT

TECHNOLOGY LABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LABORATORIES, INC. 301 North Howes

Fort Collins, Colorado 80521

Sample ID:

MW No. 1 H₂O

Sampled: Received: 10/26/94

Analyzed:

10/26/94 10/26/94

Project No:

24947002

Lab ID:

8466-1

Compound AnalyzedConcentration (mg/L)Method (Detection Limit)TVPH (Purgeable)<0.5</td>EPA-8015 Modified (0.5 mg/L)TEPH (Extractable)<0.5</td>EPA-8015 Modified (0.5 mg/L)Oil and Grease<5</td>EPA-413.1 (5 mg/L)

Bule Genery TECHNOLOGY LABORATORY, INC.

TECHNOLOGY LABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LABORATORIES, INC. 301 North Howes

Fort Collins, Colorado 80521

Sample ID:

MW No. 1 H₂O

Lab ID:

8466-1

Sampled: Received: 10/26/94 10/26/94

Analyzed:

10/27/94

Project No.:

24947002

Method:

EPA-8260

CAS Number	Compound Analyzed	Concentration µg/L	CAS Number	Compound Analyzed	Concentration µg/L
75-01-4	Vinylchloride	<0.5	127-18-4	Tetrachloroethene	< 0.5
74-87-3	Chloromethane	< 0.5	106-93-4	1,2-dibromoethane	1.1
74-83-9	Bromomethane	< 0.5	124-48-1	Dibromochloromethane	< 0.5
75-00-3	Chloroethane	< 0.5	108-90-7	Chlorobenzene	< 0.5
75-69-4	Trichlorofluoromethane	< 0.5	630-20-6	1,1,1,2-tetrachloroethane	< 0.5
75-35-4	1,1-Dichloroethene	16.6	100-41-4	Ethylbenzene	< 0.5
156-60-5	trans-1,2-dichloroethenecis-	< 0.5		Total Xylenes	< 0.5
156-59-2	1,2-dichloroethene	< 0.5	100-42-5	Styrene	< 0.5
75-09-2	Methylene Chloride	< 0.5	75-25-2	Bromoform	< 0.5
75-34-3	1,1-Dichloroethane	20.7	79-34-5	1,1,2,2-Tetrachloroethane	< 0.5
74-97-5	Bromochloromethane	< 0.5	98-82-8	Isopropylbenzene	< 0.5
67-66-3	Chloroform	< 0.5	108-86-1	Bromobenzene	< 0.5
71-55-6	1,1,1-Trichloroethane	39.3	95-49-8	2-chlorotoluene	< 0.5
56-23-5	Carbon Tetrachloride	< 0.5	106-43-4	4-chlorotoluene	< 0.5
71-43-2	Benzene	< 0.5	108-67-8	1,3,5-trimethylbenzene	< 0.5
107-06-2	1,2-Dichloroethane	5.8	95-63-6	1,2,4-trimethylbenzene	< 0.5
79-01-6	Trichloroethene	5.3	98-06-6	tert-butylbenzene	< 0.5
78-87-5	1,2-Dichloropropane	< 0.5	135-98-8	sec-butylbenzene	< 0.5
75-27-4	Bromodichloromethane	< 0.5	106-46-7	1,4-dichlorobenzene	< 0.5
74-95-3	Dibromomethane	< 0.5	541-73-1	1,3-dichlorobenzene	< 0.5
108-88-3	Toluene	< 0.5	99-87-6	4-isopropyltoluene	< 0.5
79-00-5	1,1,2-Trichloroethane	< 0.5	104-51-8	n-butylbenzene	< 0.5
78-87-5	1,3-dichloropropane	< 0.5	87-61-6	1,2,3-trichlorobenzene	< 0.5
594-20-7	2,2-dichloropropane	< 0.5	120-82-1	1,2,4-trichlorobenzene	< 0.5
563-58-6	1,1-dichloropropene	< 0.5	87-68-3	Hexachlorobutadiene	< 0.5
542-75-6	cis-1,3-dichloropropene	< 0.5	91-20-3	Naphthalene	1.5
542-75-6	trans-1,3-dichloropropene	< 0.5	95-50-1	1,2-Dichlorobenzene	< 0.5

TECHNOLOGY LABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

Sample ID:

MW No. 1 H₂O

Project No.:

24947002

Lab ID:

8466-1

Method:

EPA-8260

SURROGATE RECOVERIES

Compound	% Recovery	% Rec. Limits
Dibromofluoromethane	101	76-114
Toluene-d ₈	104	88-110
4-Bromofluorobenzene	108	86-115

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LABORATORIES, INC.

Sampled: 10/26/94

301 North Howes Received: 10/26/94

Fort Collins, Colorado 80521 Analyzed: 10/27/94

Sample ID: MW No. 1 H₂O Project No.: 24947002

Lab ID: 8466-1

Compound Analyzed Concentration (mg/L) Method Dissolved Arsenic < 0.005 EPA-7060 Dissolved Barium < 0.1 EPA-7080 Dissolved Cadmium < 0.01 EPA-7130 Dissolved Chromium < 0.01 EPA-7190 Dissolved Selenium < 0.005 EPA-7741 Dissolved Silver < 0.01 EPA-7760 Dissolved Mercury < 0.005 EPA-7470 Dissolved Lead < 0.003 EPA-7420

Bile Friend TECHNOLOGY LABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LAB 301 North How Fort Collins, C			Sampled: Received: Analyzed:	10/26/94 10/26/94 10/28/94
Sample ID:	MW No. 1 H ₂ O		Project No.:	24947002
Lab ID:	8466-1		Method:	EPA-8080
Cas Number		Compound Analyzed	Concentration µg/L	3 (1)
12674-11-2 11104-28-2 11141-16-5 53469-21-9 12672-29-6 11097-69-1 11096-82-5		Aroclor-1016 Aroclor-1221 Aroclor-1232 Aroclor-1242 Aroclor-1248 Aroclor-1254 Aroclor-1260	<1.0 <1.0 <1.0 <1.0 <1.0 <1.0 <1.0	

Bill Grey TECHNOLOGY IGBORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LABORATORIES, INC.

301 North Howes

Fort Collins, Colorado 80521

Sample ID:

Lab ID:

MW No. 2 H₂O

8466-2

Sampled:

10/26/94

Received:

10/26/94

Analyzed:

10/26/94

Project No:

24947002

Compound Analyzed	Concentration (mg/L)	Method (Detection Limit)
TVPH (Purgeable) TEPH (Extractable) Oil and Grease	<0.5 <0.5 <5	EPA-8015 Modified (0.5 mg/L) EPA-8015 Modified (0.5 mg/L) EPA-413.1 (5 mg/L)

TECHNOLOGY LABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LABORATORIES, INC.

301 North Howes

Fort Collins, Colorado 80521

Sample ID:

MW No. 2 H₂O

Lab ID:

8466-2

Sampled: Received: 10/26/94 10/26/94 10/27/94

Analyzed:

Project No.:

24947002

Method:

EPA-8260

CAS Number	Compound Analyzed	Concentration µg/L	CAS Number	Compound Analyzed	Concentration µg/L
75-01-4	Vinylchloride	<0.5	127-18-4	Tetrachloroethene	108
74-87-3	Chloromethane	< 0.5	106-93-4	1,2-dibromoethane	< 0.5
74-83-9	Bromomethane	< 0.5	124-48-1	Dibromochloromethane	< 0.5
75-00-3	Chloroethane	< 0.5	108-90-7	Chlorobenzene	< 0.5
75-69-4	Trichlorofluoromethane	< 0.5	630-20-6	1,1,1,2-tetrachloroethane	< 0.5
75-35-4	1,1-Dichloroethene	< 0.5	100-41-4	Ethylbenzene	0.9
156-60-5	trans-1,2-dichloroethenecis-	< 0.5		Total Xylenes	1.6
156-59-2	1,2-dichloroethene	< 0.5	100-42-5	Styrene	< 0.5
75-09-2	Methylene Chloride	< 0.5	75-25-2	Bromoform	< 0.5
75-34-3	1,1-Dichloroethane	< 0.5	79-34-5	1,1,2,2-Tetrachloroethane	< 0.5
74-97-5	Bromochloromethane	< 0.5	98-82-8	Isopropylbenzene	< 0.5
67-66-3	Chloroform	< 0.5	108-86-1	Bromobenzene	< 0.5
71-55-6	1,1,1-Trichloroethane	< 0.5	95-49-8	2-chlorotoluene	< 0.5
56-23-5	Carbon Tetrachloride	< 0.5	106-43-4	4-chlorotoluene	< 0.5
71-43-2	Benzene	< 0.5	108-67-8	1,3,5-trimethylbenzene	2.8
107-06-2	1,2-Dichloroethane	< 0.5	95-63-6	1,2,4-trimethylbenzene	9.6
79-01-6	Trichloroethene	<0.5	98-06-6	tert-butylbenzene	1.3
78-87-5	1,2-Dichloropropane	< 0.5	135-98-8	sec-butylbenzene	< 0.5
75-27-4	Bromodichloromethane	< 0.5	106-46-7	1,4-dichlorobenzene	< 0.5
74-95-3	Dibromomethane	< 0.5	541-73-1	1,3-dichlorobenzene	< 0.5
108-88-3	Toluene	< 0.5	99-87-6	4-isopropyltoluene	< 0.5
79-00-5	1,1,2-Trichloroethane	< 0.5	104-51-8	n-butylbenzene	< 0.5
78-87-5	1,3-dichloropropane	< 0.5	87-61-6	1,2,3-trichlorobenzene	< 0.5
594-20-7	2,2-dichloropropane	< 0.5	120-82-1	1,2,4-trichlorobenzene	< 0.5
563-58-6	1,1-dichloropropene	< 0.5	87-68-3	Hexachlorobutadiene	< 0.5
542-75-6	cis-1,3-dichloropropene	< 0.5	91-20-3	Naphthalene	5.6
542-75-6	trans-1,3-dichloropropene	< 0.5	95-50-1	1,2-Dichlorobenzene	< 0.5

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

Sample ID:

MW No. 2 H₂O

Project No.:

24947002

Lab ID:

8466-2

Method:

EPA-8260

SURROGATE RECOVERIES

Compound % Recovery % Rec. I	HIIILS
Dibromofluoromethane 102 76-114 Toluene-d ₈ 104 88-110 4-Bromofluorobenzene 110 86-115	

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LABORATORIES, INC.

Sampled: 10/26/94
301 North Howes
Received: 10/26/94
Fort Collins, Colorado 80521

Analyzed: 10/27/94

Sample ID: MW No. 2 H₂O

Project No.: 24947002

Lab ID: 8466-2

Compound Analyzed	Concentration (mg/L)	Method
Dissolved Arsenic	< 0.005	EPA-7060
Dissolved Barium	<0.1	EPA-7080
Dissolved Cadmium	< 0.01	EPA-7130
Dissolved Chromium	< 0.01	EPA-7190
Dissolved Selenium	< 0.005	EPA-7741
Dissolved Silver	< 0.01	EPA-7760
Dissolved Mercury	< 0.005	EPA-7470
Dissolved Lead	< 0.003	EPA-7420

Bue frey TECHNOLOGY LABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LAB 301 North Hov Fort Collins, C			Sampled: Received: Analyzed:	10/26/94 10/26/94 10/28/94
Sample ID:	MW No. 2 H ₂ O		Project No.:	24947002
Lab ID:	8466-2		Method:	EPA-8080
Cas Number		Compound Analyzed	Concentration <u>µg/L</u>	
12674-11-2 11104-28-2 11141-16-5 53469-21-9 12672-29-6 11097-69-1 11096-82-5		Aroclor-1016 Aroclor-1221 Aroclor-1232 Aroclor-1242 Aroclor-1248 Aroclor-1254 Aroclor-1260	<1.0 <1.0 <1.0 <1.0 <1.0 <1.0 <1.0	

Bee Friend TECHNOLOGY LABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LABORATORIES, INC.

301 North Howes

Sample ID:

Lab ID:

Fort Collins, Colorado 80521

MW No. 3 H₂O

8466-3

Sampled:

10/26/94

Received:

10/26/94

Analyzed:

10/26/94

Project No:

24947002

Compound Analyzed	Concentration (mg/L)	Method (Detection Limit)
TVPH (Purgeable) TEPH (Extractable) Oil and Grease	<0.5 <0.5 <5	EPA-8015 Modified (0.5 mg/L) EPA-8015 Modified (0.5 mg/L) EPA-413.1 (5 mg/L)

TECHNOLOGY LABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LABORATORIES, INC. 301 North Howes

Fort Collins, Colorado 80521

Sample ID:

MW No. 3 H₂O

Lab ID:

8466-3

Sampled: Received: 10/26/94 10/26/94

Analyzed:

10/27/94

Project No.:

24947002

Method:

EPA-8260

CAS Number	Compound Analyzed	Concentration µg/L	CAS Number	Compound Analyzed	Concentration
75-01-4	Vinylohlonida	-0.5	107.10	,	
73-01-4 74-87-3	Vinylchloride Chloromethane	<0.5	127-18-4	Tetrachloroethene	< 0.5
		< 0.5	106-93-4	1,2-dibromoethane	< 0.5
74-83-9	Bromomethane	< 0.5	124-48-1	Dibromochloromethane	< 0.5
75-00-3	Chloroethane	<0.5	108-90-7	Chlorobenzene	< 0.5
75-69-4	Trichlorofluoromethane	<0.5	630-20-6	1,1,1,2-tetrachloroethane	< 0.5
75-35-4	1,1-Dichloroethene	<0.5	100-41-4	Ethylbenzene	1.2
156-60-5	trans-1,2-dichloroethene	< 0.5	deer our o	Total Xylenes	6.9
156-59-2	cis-1,2-dichloroethene	< 0.5	100-42-5	Styrene	< 0.5
75-09-2	Methylene Chloride	< 0.5	75-25-2	Bromoform	< 0.5
75-34-3	1,1-Dichloroethane	< 0.5	79-34-5	1,1,2,2-Tetrachloroethane	< 0.5
74-97-5	Bromochloromethane	< 0.5	98-82-8	Isopropylbenzene	< 0.5
67-66-3	Chloroform	< 0.5	108-86-1	Bromobenzene	< 0.5
71-55-6	1,1,1-Trichloroethane	< 0.5	95-49-8	2-chlorotoluene	< 0.5
56-23-5	Carbon Tetrachloride	< 0.5	106-43-4	4-chlorotoluene	< 0.5
71-43-2	Benzene	2.2	108-67-8	1,3,5-trimethylbenzene	0.8
107-06-2	1,2-Dichloroethane	< 0.5	95-63-6	1,2,4-trimethylbenzene	3.0
79-01-6	Trichloroethene	< 0.5	98-06-6	tert-butylbenzene	0.6
78-87-5	1,2-Dichloropropane	< 0.5	135-98-8	sec-butylbenzene	< 0.5
75-27-4	Bromodichloromethane	< 0.5	106-46-7	1,4-dichlorobenzene	< 0.5
74-95-3	Dibromomethane	< 0.5	541-73-1	1,3-dichlorobenzene	< 0.5
108-88-3	Toluene	5.5	99-87-6	4-isopropyltoluene	< 0.5
79-00-5	1,1,2-Trichloroethane	< 0.5	104-51-8	n-butylbenzene	< 0.5
78-87-5	1,3-dichloropropane	< 0.5	87-61-6	1,2,3-trichlorobenzene	< 0.5
594-20-7	2,2-dichloropropane	< 0.5	120-82-1	1,2,4-trichlorobenzene	< 0.5
563-58-6	1,1-dichloropropene	< 0.5	87-68-3	Hexachlorobutadiene	< 0.5
542-75-6	cis-1,3-dichloropropene	< 0.5	91-20-3	Naphthalene	2.6
542-75-6	trans-1,3-dichloropropene	< 0.5	95-50-1	1,2-Dichlorobenzene	< 0.5

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

Sample ID:

MW No. 3 H₂O

Project No.:

24947002

Lab ID:

8466-3

Method:

EPA-8260

SURROGATE RECOVERIES

Compound	% Recovery	% Rec. Limits
Dibromofluoromethane	98	76-114
Toluene-d ₈	104	88-110
4-Bromofluorobenzene	110	86-115

Bie Friend TECHNOLOGY JABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

EMPIRE LABORATORIES, INC. 301 North Howes

Fort Collins, Colorado 80521

Sample ID: MW No. 3 H₂O

Lab ID: 8466-3 Sampled: Received:

10/26/94 10/26/94

Analyzed: 10/27/94

Project No.: 24947002

Compound Analyzed	Concentration (mg/L)	Method
Dissolved Arsenic Dissolved Barium Dissolved Cadmium Dissolved Chromium Dissolved Selenium Dissolved Silver Dissolved Mercury Dissolved Lead	<0.005 <0.1 <0.01 <0.01 <0.005 <0.005 <0.005 <0.0005 <0.0005	EPA-7060 EPA-7080 EPA-7130 EPA-77190 EPA-7741 EPA-7760 EPA-7470
		EPA-7420

HNOLOGY/LABORATORY, INC.

CENTRE FOR ADVANCED TECHNOLOGY

2401 Research Boulevard, Suite 204 Fort Collins, Colorado 80526 (303) 490-1414

WATER ANALYSIS REPORT

301 North Hov	ORATORIES, INC. ves colorado 80521		Sampled: Received: Analyzed:	10/26/94 10/26/94 10/28/94
Sample ID:	MW No. 3 H ₂ O		Project No.:	24947002
Lab ID:	8466-3		Method:	EPA-8080
Cas Number		Compound Analyzed	Concentration $\mu g/L$	
12674-11-2 11104-28-2	logisM	Aroclor-1016 Aroclor-1221	<1.0 <1.0	
11104-26-2		Aroclor-1232	<1.0	
53469-21-9		Aroclor-1232 Aroclor-1242	<1.0	
12672-29-6		Aroclor-1248	<1.0	
11097-69-1		Aroclor-1254	<1.0	

Aroclor-1260

Brie Kney TECHNOLOGY LABORATORY, INC.

11096-82-5





JIM GERINGER GOVERNOR

Department of Environmental Quality

Herschler Building

122 West 25th Street

Cheyenne, Wyoming 82002

ADMINISTRATION (307) 777-7758 FAX 777-7682 ABANDONED MINES (307) 777-6145 FAX 634-0799 AIR QUALITY (307) 777-7391 FAX 777-7682 (307) 777-7368 FAX 777-6937 LAND QUALITY (307) 777-7756 FAX 634-0799 SOLID & HAZARDOUS WASTE (307) 777-7752 FAX 777-5973 WATER QUALITY (307) 777-7781 FAX 777-5973

September 27, 1995

Scott M. Nelson
Executive Vice President and General Counsel
Blood Systems, Inc.
6210 E. Oak St.
P.O. Box 1867
Scottsdale, AZ 85252-1867

Re: Lot 1, Block 4, Cheyenne Airport Addition August 10, 1995, Blood Systems' Letter

Dear Mr. Nelson:

The Wyoming Department of Environmental Quality, Water Quality Division (WDEQ/WQD) has reviewed the referenced letter. I did speak with Bob Roberson in regards to this matter. The WDEQ/WQD does concur that the concentration levels of chlorinated solvents and the other contaminants that were sampled during the Phase 1 study exceed State Groundwater Standards, but remediation activities are not warranted at this time. The site characterization and sampling that was conducted was not extensive enough to determine the location of the source; although, it was proposed that the source was located upgradient and northwest of the site.

Based upon previous investigations, WDEQ/WQD is aware of chlorinated solvent contamination in the area and beneath the property. However, the WDEQ has not identified the source(s) of the contamination. Please be advised that WDEQ's files containing information on the contamination are available for inspection by Blood Systems, Inc. representatives.

WDEQ/WQD can't confirm written statement No. 3 outlined on page 2 of your letter. WDEQ/WQD doesn't have control over all situations that may require a current and/or future owner to be responsible for site remediation. Additional investigations in the future may reveal extensively contaminated areas that would require remedial actions under EPA or State jurisdiction (i.e., CERCLA, RCRA, etc.).

September 27, 1995 Page 2

WDEQ/WQD is available to discuss further any topics regarding this matter. Please do not hesitate to call about any questions that you may have.

Sincerely,

Phillip Stump Phillip Stump

Senior Environmental Analyst

PS:ks 54300.ltr

cc: Kevin Frederick, Supervisor, Groundwater Pollution Control Program

6210 E. Oak St. / P.O. Box 1867 / Scottsdale, AZ 85252-1867 (602) 946-4201 / FAX (602) 941-2198

August 10, 1995

Mr. Phil Stump
Wyoming Department of Environmental Quality
Water Quality Division
122 W. 25th Street
Herschler Bldg., Fourth Floor - West Wing
Cheyenne, WY 82002

AUG 17 195

Re:

Lot 1, Block 4, Cheyenne Airport Addition

Cheyenne, Wyoming

Dear Mr. Stump:

I am writing on behalf of Blood Systems, Inc., dba United Blood Services, a non-profit corporation. United Blood Services in Cheyenne, Wyoming recently purchased a vacant parcel of property to construct a new blood center. The property is next to the Cheyenne airport and located north of 8th Avenue, west of Warren Avenue and east of Central Avenue. At the present time, we are applying for financing in which the Cheyenne property will serve as collateral. In connection with our application for financing, the bank has reviewed the environmental reports relating to the property. I believe that Mr. Bob Roberson from Bank One-Arizona called you last week to discuss these matters.

Prior to purchasing the property in Cheyenne, a Phase I Environmental Site Assessment was performed by Inberg-Miller Engineers. Based on the information obtained by the Phase I study, we contracted with Empire Laboratories, Inc. ("Empire") to conduct a Level II Site Assessment. Following the Level II study, Empire contacted the Wyoming Department of Environmental Quality/Water Quality Division ("WDEQ") to ascertain the significance of the levels of PCE, and concentrations of 1,1-dichoroethene, 1,2-dichloroethane and trichloroethene contamination observed in the groundwater samples collected at the property. The findings of the Empire Level II study were discussed with WDEQ. The Empire study concluded that based on groundwater flow direction, it appears that the PCE contamination was migrating onto the property from an upgradient source, i.e., northwest of the site. A representative of WDEQ confirmed to Empire that while PCE levels were significant, WDEQ has no plans to take action to remediate the contamination. With respect to the other contaminants observed in the groundwater samples, WDEQ's opinion was that the

levels of contamination were minimal and/or not significant and did not warrant remediation activities.

To assist United Blood Services in securing financing, Bank One has requested that we seek confirmation from WDEQ on the following matters:

- WDEQ has confirmed that groundwater contamination is present in the general area, which includes the groundwater beneath the subject property.
- WDEQ has no documentation and has no indication that past and/or present activities on the subject property have caused and/or contributed to groundwater contamination in the area or beneath the subject property.
- 3. WDEQ has no plans to take any action to remediate the contamination which is present in groundwater beneath the site and that the current, and/or future owner would not be held responsible for site remediation.

I believe that Mr. Roberson and you discussed all of these points, and I am merely following up to get a letter from you confirming the points so that we can proceed with the financing.

On behalf of United Blood Services, I appreciate your assistance in this matter. If you have any questions please let me know.

Sincerely,

SCOTT M. NELSON

Executive Vice President and General Counsel

Scatt m Nelson

and Ocheral Cou

SMN:se